

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1964

CONSERVATION DIVISION
Wichita, Kansas

4-14-1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. H. G. Pankratz of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: H-30 Drilling, Inc.

Complete Address: 200 North Main, Wichita, Kansas

Lease Name: O'Hara Well No. 1

Location: SW SW NE Sec. 26 Twp. 18 Rge. 7 (E) (W) X

County Rice Total Depth 3482' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

Fill hole with mud to 210'. Push plug and 1/4 sack hulls

to 210' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/4 sack hulls to

40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,