

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

October 23, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Roy Goans of Allen Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: R+B Petroleum, Inc.

Complete Address: Box 1065, Great Bend, Kansas 67530

Lease Name: Behnke "B" Well No. 2

Location: NW NE SE Sec. 25 Twp. 18 Rge. 7 (E) (W)

County: Rice Total Depth: 3205

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Goans was instructed to plug the well as follows:

8 5/8" - 215' - 130 sacks 60/40 Pozmix 2% gel 3% cc. Circulate hole and Fill with mud. Pump 50 sacks cement through drill pipe at 300'. Fill hole with mud to 40'. Pump plug and 1/2 sack balls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1981
10-26-1981
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

[Signature]
Conservation Division Agent