

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 16, 1966

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1966

CONSERVATION DIVISION
Wichita, Kansas

5-18-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dick Everhart of Glickman Oil Company has this date requested permission to plug the following described well:

Mr. Everhart guarantees payment of the plugging fee.

Operator's full Name: George A. Reed

Complete Address: 1301 Union National Bldg., Wichita, Kansas

Lease Name: Williams Well No. 1

Location: C SE SE Sec. 21 Twp. 18 Rge. 7 (E)(W) X

County Rice Total Depth 3472' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Everhart was instructed to plug the well as follows:

Fill hole with mud to 245'. Push plug and 1/4 sack hulls to 245' and
cement hole with 20 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

William J. Loman
Conservation Division Agent