

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

October 31, 1967

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1967

CONSERVATION DIVISION
Wichita, Kansas

11-17-1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Leo Michaelis

Complete Address: R.R. #2, Russell, Kansas 67665

Lease Name: Bain Well No. 1

Location: SE SW SE Sec. 1 Twp. 18 Rge. 8 (E) (W) X

County Rice Total Depth 3339' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

Push 4 1/2" plug to 3200'. Fill hole with sand to 3190' and cement
with 3 sacks. Fill hole with mud to 235'. Set rock bridge from 235'
to 225' and cement hole with 25 sacks. Fill hole with mud to 40'.
Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND S. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leo Michaelis of Russell, Kansas has this date requested permission to plug the following described well:

Mr. Michaelis guarantees payment of the plugging fee.

Operator's full Name: Leo Michaelis

Complete Address: R.F.D.#2 Russell, Kansas

Lease Name: BAIN Well No. 1

Location: SE SW SE Sec. 1 Twp. 18S Rge. 8 (E) (W)

County: Rice Total Depth 3335 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole Washdown

Mr. Michaelis was instructed to plug the well as follows:

contact district plugging
agent for plugging instructions
Forbes Casing Pulling Company
Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION

NOV 6 1967

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

D. S. Greider
Conservation Division Agent