

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

January 20, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1970
CONSERVATION DIVISION
Wichita, Kansas

1-27-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: George Ablah

Complete Address: 8028 Cork, Wichita, Kansas 67206

Lease Name: Hill Well No. 3

Location: ^{50'}100' NW of SW SW NW Sec. 33 Twp. 18 Rge. 7 ~~(E)~~ (W) X

County: Rice Total Depth 3570' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/2 sack hulls to 200' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Arthur J. Leonard
Conservation Division Agent