

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-159-21,307

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name R & B Petroleum, Inc.

Complete Address Box 1065, Great Bend, Kansas 67530

Lease Name Behake "B" Well-No. 2

Location NW NE SE Sec. 25 Twp. 18 Rge. 7 (~~East~~) (West)

County Rice Total Depth 3205'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company and Halliburton Co.

Address Box 1389, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 12:15 PM Day: 24 Month: October Year: 1981

Plugging Operations attended by Agent?: All  Part  None

8 5/8" - 215' - 130 sacks 60/40 Pozmix 2% gel 3% cc.

The above well was plugged as follows:

Hole circulated and filled with mud. 50 sacks 50-50 Pozmix  
with 2% gel 3% cc pumped through drill pipe at 300'  
Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed  
to 40' and hole cemented to base of cellar with 10 sacks cement.  
Pathole cemented with 10 sacks cement.

10-26-1981

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1981

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated.  
**INVOICED**

Signed: [Signature]  
Conservation Division Agent

DATE 11-23-81

INV. NO. 8451-W