

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- - OWWO

Operator's Full Name R-B Petroleum

Complete Address P.O. Box 1065, Great Bend, Kansas 67530

Lease Name Sellers Farm Well No. 1

Location NE NE NE Sec. 25 Twp. 18 Rge. 7 (~~East~~) (West)

County Rice Total Depth 3350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated OWWO

Plugging Contractor Allen Drilling Company and Sun Oil Well Cementing Co.

Address Box 1389, Great Bend, Kansas License No.

Operation Completed: Hour: 9:00 AM Day: 19 Month: June Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-260'-circ.

Hole circulated and filled with mud. 50 sacks 50-50 Pozmix w/4% gel
and 3% cal. chloride pumped through drill pipe at 300'. Hole filled
with mud to 40'. Plug and $\frac{1}{2}$ sack hulls pushed to 40' and hole cemented
to base of cellar with 10 sacks cement. Rathole cemented with 5 sacks
cement.

6-23-1981

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Albert J. Loman
Conservation Division Agent

DATE 7-23-81

INV. NO. 5922-w