


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Rice County. Sec. 13 Twp. 18 Rge. (E) 7 (W)
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines SE - NE - NE
Lease Owner Time Petroleum Company
Lease Name Bonleewe Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 7-2 19 57
Plugging completed _____ 7-6 19 57
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	None
				5 1/2	3182	2617.48

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3170 - dumped 6 sks cement - pulled pipe - mudded hole to 190' - set rock bridge - dumped 15 sks cement - mudded to 15' - dumped 5 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF _____, COUNTY OF _____, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Schreiner
500 Osphum Bldg, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1957.

My commission expires Dec 19, 1960

Marjorie Bank
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 13 T. 18 R. 7W
BOOK PAGE 23 LINE 21

JUL 16 1957
7-16-1957
CONSERVATION DIVISION
Kansas

ROTARY DRILLING LOG

OPERATOR: E. H. Riggs
 Bronkeewe #3
 NE NE NE Sec. 13-18S-7W
 Rice County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 3-12-54
 COMP: 3-23-54

FORMATION

REMARKS

Clay & Surface Rock	40
Sand	60
Shale	90
Shale & Shells	208
Lime	220
Shale W/Shells	245
Red Rock	390
Red Rock & Shells	440
Shale & Shells	935
Shale & Shell	1015
Sand	1350
Lime W Shale Breaks	1465
Shale & Lime	1745
Shale W/Lime Streaks	1990
Shale & Lime	2245
Shale W/Lime Streaks	2280
Lime W/Shale Breaks	2315
Lime & Shale	2340
Lime W/Shale Breaks	2402
Lime & Shale	2435
Lime W/Shale Breaks	2495
Lime & Shale	2570
Lime W/Shale Breaks	2610
Shale W/Lime Streaks	2725
Lime & Shale	2805
Lime W/Shale Breaks	2915
Shale W/Lime	2960
Lime	3030
Lime & Shale	3140
Shale & Sand	3176
Shale & Sand	3270
Total Depth	3270

Run 10 joints of 8-5/8" casing; set at 210', cemented with 125 sax Portland 2% CC.

Run 104 joints 5-1/2" 14" J-55; set @ 3270'; cemented with 75 sax pozmix.

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

BY R. R. McNeil

RECEIVED
 STATE CORPORATE COMMISSION
 JUN 27 1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 13 T 18 R 7W
 BOOK PAGE 23 LINE 21