

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-21, 978-00-00

LEASE NAME Gray

WELL NUMBER 2

4950 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 9 TWP. 18 RGE. 7 (#) or (W)

COUNTY Rice

Date Well Completed 3-6-85

Plugging Commenced 12-3-90

Plugging Completed 12-17-90

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR J D Production Co.

ADDRESS Box 309, Geneseo, Kansas 67444

PHONE# (316) 824-6204 OPERATORS LICENSE NO. 8917

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-5-90 (date)

by Ralph Tittel (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3251 Bottom 3410 T.D. 3410

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	276	8 5/8		
		0	3342	5 1/2		

STATE 1-25-1991
1441 2-5-1991
0
2,494 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Fill with sand to 3292 ft. & dump 5 sxs. cement.
ump 30 sxs. cement @ 950 ft., then pump 30 sxs. cement @ 700 ft., then
pump 40 sx. cement @ 300 ft., then circulate from 80 ft. to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address P.O. Box #2 108, Geneseo, Kansas 67444

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J D Production Co.

STATE OF Kansas COUNTY OF Rice, ss.


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Allen D. Dickel as

(Address) Box 108, Geneseo, Ks 67444

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 19 91

Marsha S. Huggans
Notary Public



My Commission Expires: September 1, 1994