


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 26 Twp. 18S Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Beardmore Drilling Company
Lease Name Kern Well No. 1
Office Address 827 Beacon Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-2 19 57
Application for plugging filed 6-2 19 57
Application for plugging approved 6-2 19 57
Plugging commenced 6-2 19 57
Plugging completed 6-2 19 57
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3252 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0'	40'			
Sand		40'	80'			
Shale and Shells		80'	212'	8-5/8"	212'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0 to 30' - 5 sxs cement
30' - Wood Plug
30' to 155' - Heavy Mud
155' to 200' - 15 sxs cement
200' - Wood Plug
200' to 3252' - Heavy Mud

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company
Address 827 Beacon Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
827 Beacon Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of June, 1957

My commission expires January 28, 1960

Leonard P. Tolle
Notary Public.

JUN 14 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. _____ T. _____ R. _____
BOOK PAGE _____ LINE _____

6-14-1957

BEARDMORE-FARRIS-PATTON-ET AL

#1 Kern
NE NW NW Sec. 26-18S-9W
Rice County, Kansas

Drilled By: Beardmore Drilling Company
Drilling Commenced: 5-24-57
Drilling Completed: 6-3-57

CASING; 8-5/8" set at 212' with 130 sxs cement. Cement circulated 5-24-57.

ELEVATION: KB 1726
DF 1723
Gr 1721

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Soil and Clay	40
Sand	80
Shale and Shells	212
R.B. Shale and Shells	525
Shale and Shells	1200
Shale and Lime	1490
Shale and Lime	2410
Shale and Lime	2805
Shale and Lime	2960
Lime	2985
Lime	3060
Shale and Lime	3140
Lime	3190
Shale and Lime	3210
Coring	3252
Rotary Total Depth	3252


TOPS

Heebner	2728
Toronto	2749
Brown Lime	2855
Lansing	2884
Conglomerate	3215
Simpson Shale	3227
Simpson Sandstone	3239

- DST #1 2898-2975 - Open 1 hr., shut in 20 min., good blow, packer leaked, reset packer, gas in 20 min. Recovered 600' gas cut mud, no water, no oil. IF 180, FF 250, FBHP 1005.
- DST #2 3024-3059 - Open 1 hr., shut in 20 min. Recovered 65' watery mud, few spots oil. IF 30, FF 40, IBHP 1345, FBHP 175.
- CORE #1 3210-3223 - Recover 13'
- CORE #2 3223-3238 - Recover 15'
- CORE #3 3238-3252 - Recover 14'
- DST #3 3214-3252 - Shut in 20 min., open 1 hr., shut in 20 min. Recovered 180' slightly oil cut mud, considerable water, 30' slightly oil and gas cut mud, some water, 180' heavy oil and gas cut mud, 40% water. BHP 950#.

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.



Subscribed and sworn to before me this 10th day of June, 1957.


Leonard P. Tolle-Notary Public

My Commission Expires:
January 28, 1960

PLUGGING			
FILE	SEC	26	18 9W
BOOK	PAGE	19	LINE 31