

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 B. King Building
Wichita, Kansas

Rice County. Sec. 26 Twp. 18S Rge. (E) 9 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SW SW NW

Lease Owner Donald T. Ingling, et al

Lease Name Kern Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-17-52 19

Application for plugging filed 5-5-52 19

Application for plugging approved 5-5-52 19

Plugging commenced 5-5-52 19

Plugging completed 5-9-52 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee

Producing formation Depth to top Bottom Total Depth of Well 3288 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5-1/2" | 3273' | 2609' |
| | | | | 8 5/8" | 196' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 2960' to 2890' and ran 6 sacks of cement. Mudded hole to 190', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 20' and ran 5 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

D. T. Ingling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

611 Orpheum Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 20th day of May, 1952

My commission expires February 27, 1956

23-8390-s 6-51-20M

PLUGGING
FILE SSC 26T 18R 9W
BOOK PAGE 15 LINE 42

[Signature] Notary Public.
STATE CORPORATION COMMISSION

MAY 21 1952

CONSERVATION DIVISION
Wichita, Kansas

5-21-1952

WELL LOG ----- KERN NO. 1

Donald T. Ingling et al, Lease Owner

Sec. 26, Twsp. 18S, Rnge. 9W

Donald T. Ingling, Contractor

Location: C SW SW NW

Commenced: February 19, 1952

County: Rice, Kansas

Completed: March 7, 1952 (Restoring)

Production: DRY

Casing: 8 5/8" = 196'

Elevation: 1720 D.F.

5 1/2" = 3273'

Total Depth: 3288' (Restoring)

Figures below indicate bottom of formation:

| | | | |
|------|--------------------|------|--------------------------------|
| 40 | Surface clay | 2705 | Lime |
| 60 | Sand | 2745 | Lime |
| 165 | Shale | 2800 | Lime |
| 196 | Shale and shells | 2845 | Lime |
| 350 | Shale | 2885 | Lime and sand |
| 450 | Red rock and shale | 2925 | Lime |
| 945 | Shale and shells | 2970 | Lime |
| 1000 | Shale | 2974 | Lime |
| 1090 | Salt and shale | 3005 | Lime |
| 1195 | Shale and shells | 3035 | Lime |
| 1285 | Lime and shale | 3070 | Lime |
| 1375 | Lime and shale | 3100 | Lime |
| 1475 | Shale and lime | 3130 | Lime |
| 1570 | Lime and shale | 3153 | Lime |
| 1630 | Lime | 3180 | Lime |
| 1760 | Lime and shale | 3210 | Lime |
| 1840 | Shale | 3233 | Conglomerate |
| 1935 | Lime and shale | 3250 | Conglomerate and Simpson Shale |
| 2020 | Lime and shale | 3271 | Conglomerate |
| 2235 | Lime and shale | 3280 | Arbuckle Lime |
| 2360 | Lime and shale | 3288 | Lime |
| 2450 | Shale and lime | 3288 | Total Depth |
| 2510 | Lime and shale | | |
| 2575 | Lime and shale | | |
| 2620 | Lime | | |
| 2670 | Lime | | |

PLUGGING
 FILE SEC 26 T 18 R 9 W
 BOOK PAGE 15 LINE 42

I hereby certify that this is a true and correct log of the above mentioned well.

DONALD T. INGLING

STATE OF KANSAS

COUNTY OF SEDGWICK

ss

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1952

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a Notary public insaid County and State this 10th day of March, 1952

Donald T. Ingling

W.E. Black
Notary Public

My commission expires

February 27, 1956