

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rice SEC. 26 TWP. 18 RGE. 9 ~~E/W~~
 Location as in quarters or footage from lines:

Lease Owner ENERGY OIL AND GAS INC
 Lease Name STEFFEN Well No. B #1
 Office Address P. O. Box 121, Rago, Kansas 67128
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed July 21, 1981
 Application for plugging filed July 21, 1981
 Plugging commenced July 21, 1981
 Plugging completed July 21, 1981
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3279
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

~~XXXXXXXXXXXX~~ Bottom Plug set at 540' w/50 sacks cement thru drill pipe
 Middle Plug set at 240' w/30 sacks cement
 Top Plug set at 40' w/~~10~~ 10 sacks cement

RECEIVED 7-24-1981
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Darrel Anderson (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.
 (Signature) Darrel Anderson
P.O. Box 823 - Great Bend, Ks. 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 23 day of July, 19 81

Dorothy M. Hogue
 Notary Public.

My Commission expires: April 11, 1982

DRILLERS WELL LOG

DATE COMMENCED: July 14, 1981
 DATE COMPLETED: July 21, 1981

Energy Oil & Gas Inc.
 Steffan B-1
 SE SW NW
 Sec. 26 - T18s - R9w
 Rice County, KS

0 - 245' Surface soil, Shale
 245 - 2725' Shale & Lime
 2725 - 2727' Shale
 2727 - 2880' Lime & Shale
 2880 - 3163' Lime
 3163 - 3231' Shale, Lime, Conglomerate
 3231 - 3279' Sand, Shale
 3279' RFD

ELEVATION:

FORMATION DATA

Heebner	2725'
Iatan	2856'
Lansing	2880'
Base K.C.	3163'
Conglomerate	3190'
1st Simpson Sand	3231'
Base Simpson	3256'
RFD	3279'

Surface Pipe: Set new 20#
 8-5/8" pipe at 296' with
 175 sacks Quick-set

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Darrell Anderson of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Darrell Anderson

Subscribed and sworn to before me this 23 day of July, 1981.

My Comm. Expires:

4-11-1982

Verity M. Hague
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 22 1981
 CONSERVATION DIVISION
 Wichita, Kansas