

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-20,760-00-00

LEASE NAME KERN

WELL NUMBER #1

SPOT LOCATION SE NW SW

SEC. 26 TWP. 18S RGE. 9 (X) or (W)

COUNTY Rice

Date Well Completed _____

Plugging Commenced 10/31/84

Plugging Completed 10/31/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS P. O. Box 288, Russell, KS 67665

PHONE # (913) 483-5371 OPERATORS LICENSE NO. 6033

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #5, Salina

Is ACO-1 filed? No if not, is well log attached? Yes

Producing formation Conglomerate Depth to top 3240' bottom 3265' T.D. 3320'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Herrington	Oil & wtr	1285'		8 5/8"	243'	0'
Heebner	Oil & wtr	2730'	2751'			
Lansing	Oil & wtr	2884'	3168'	4 1/2"	3318'	0'
Conglomerate	Oil & wtr	3240'	3265'			
Arbuckle	Oil & wtr	3294'	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged inside 4 1/2" casing w/2 sx hulls, 25 sx 50/50 Pozmix w/4% gel., 55 sx 50/50 Pozmix w/4% gel. Max psi = 2000#. Shut in psi = 1000#. Have cement in casing from surface to 760'; Gel from 760' to 3075' Cement from 3075' to TD. Plugged between 4 1/2" & 8 5/8" csg w/6 sx hulls, 75 sx 50/50 Pozmix w/4% gel.

Plugging was witnessed and approved by Merlan Unruh, from KCC Dist. #5.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address P. O. Box 288,

Russell, Kansas 67665


STATE OF Kansas COUNTY OF Russell, ss.

John C. Niernberger (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) John C. Niernberger

(Address) P. O. Box 288, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 15 day of Nov., 1984



Kerran Redington
Notary Public

My Commission expires: 2/6/86