


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

### WELL PLUGGING RECORD OR FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
of formations.

*pd*  
*5/22/40*  
*Ka*

NORTH



Locate well correctly on above  
Section Flat

*Rice* County. Sec. *26* Twp. *18* Rge. *9* (E) (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines *Cor. W. 1/2 NW 1/4 SE 1/4*  
Lease Owner *Comanche Oil Co. & Crow Drilling*  
Lease Name *Monroe* Well No. *1*  
Office Address *Wichita Kansas*  
Character of Well (Completed as Oil, Gas or Dry Hole) *Dry Hole*  
Date, well completed *May 10* 193*40*  
Application for plugging filed *yes* 193  
Application for plugging approved 193  
Plugging Commenced *MAY 11* 193*40*  
Plugging Completed *MAY 11* 193*40*  
Reason for abandonment of well or producing formation *Dry Hole*

If a producing well is abandoned, date of last production *None* 193  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well *R. Karkee*  
Producing formation *None* Depth to top Bottom Total Depth of Well *330* Feet.  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<i>250 Ft 8 5/8" SURFACE CASING</i>						


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

*Hole was filled with heavy Rotary Mud. Dry hole Plug placed in bottom of SURFACE CASING AT 245 FT. 20 Sack Cement dumped ON TOP hole filled to with IN 20 FT OF THE TOP with heavy Rotary Mud. The second dry hole Plug placed there & 10 Sack Cement PLACED ON TOP OF THIS PLUG AND GAP welded over TOP OF CASING.*

*7-10-1940*

*pd*  
*5/22/40*  
*Ka*

PLUGGING  
FILE SEC *26-18-94*  
BOOK PAGE *103* LINE *2*



(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to *Comanche Oil Co. Wichita, Kans. or Crow Drilling Co. Hoisington, Kans.*  
Address \_\_\_\_\_

STATE OF *Kansas* COUNTY OF *Adair*, ss.  
*Glenn H. Beck* (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Crow Drilling Co. By Glenn H. Beck*  
*Hoisington, Kansas*  
(Address)

SUBSCRIBED AND SWORN to before me this *9* day of *July*, 19*40*

My commission expires *6.6.42*  
*W. Woodward* Notary Public.

Well - No. 1 Monroe - Center West Half Northwest Quarter Southeast Quarter (C W $\frac{1}{2}$  NW SE)  
Section 26-18-9W, Rice County, Kansas

Companies - Comanche Oil Co., Inc., Crow Drilling Co., and Derby Oil Co.  
Contractor - Crow Drilling Company  
Commenced - April 24, 1940  
Completed - May 10, 1940  
Total Depth - 3330'  
Initial production - Dry and Abandoned  
Elevation - 1731'

" 152 Pipe record

LOG- Formation	Depth
Clay, sand, shale	0-108
Shale and shells	255
Red bed	378
Anhydrite	393
Shale and shells	510
Shale	775
Salt & shale	1080
Salt	1120
Shale	1140
Anhydrite	1270
Shale and shells	1375
Lime and shale	1451
Shale	1480
Dolomite	1567
Brown Sandy Lime	1598
Shale and lime	1615
Sandy lime and shale	1637
Lime and shale	2223
Lime	2293
Shale	2366
Lime and shale	2400
Shale and shells	2424
Lime	2490
Lime and shale	2585
Lime	2763
Shale and lime	2826
Shale	2850
Shale and shells	2873
Lime, streaks shale	2908
Lime	2995
Lime, soft	3007
Lime	3165
Lime and Chert	3183
Lime	3215
Conglomerate	3285
Sandy Chert	3288
Conglomerate & sand strks	3306
Shale & lime	3323
Arbuckle lime	3330 TD

Now comes Perry A. Thayer, who states that he is familiar with drilling of oil and gas wells and he personally knows that the Monroe No. 1 in Center West Half Northwest Quarter Southeast Quarter (C W $\frac{1}{2}$  NW $\frac{1}{4}$  SE $\frac{1}{4}$ ) of Section 26-18-9W, Rice County, Kansas, was drilled to a depth of 3330 feet with Rotary Equipment.

*Perry A. Thayer*  
Perry A. Thayer

Show Water - D&A

State of Kansas )  
County of Sedgwick ) ss.

PLUGGING  
FILE SEC 26-18-9W  
BOOK PAGE 103 LINE 2



BE IT REMEMBERED, that on this 15 day of May, 1940, before me, a Notary Public, in and for said County and State, personally appeared Perry A. Thayer known to me to be the identical person, and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes set forth.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my official seal the day and year last above written.

*W. Woodward*  
Notary Public

My commission expires 6-6-42