

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavits  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 15 Twp. 18 Rge. 9 (E) W(W)

Location as "NE/CNW%SW%" or footage from lines SE SW SE

Lease Owner Beardmore Drilling Company

Lease Name Colladay Well No. 2

Office Address 827 Beacon Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 5-20 19 58

Application for plugging filed \_\_\_\_\_ 5-20 19 58

Application for plugging approved \_\_\_\_\_ 5-20 19 58

Plugging commenced \_\_\_\_\_ 5-20 19 58

Plugging completed \_\_\_\_\_ 5-20 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3286 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Soil & Clay		0	30'			
Sand		30'	80'			
Shale & Shells		80'	223'	8-5/8"	223'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

0' to 40' - 10 sacks cement

40' - Wood Plug

40' to 140' - Heavy Mud

140' to 200' - 20 sacks cement

200' - Wood Plug

200' to 3286' - Heavy Mud

6-5-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company

Address 827 Beacon Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Heber Beardmore (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

827 Beacon Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 58

Leonard P. Tolle

Leonard P. Tolle - Notary Public.

My commission expires January 28, 1960

PLUGGING  
FILE SEC 15 T 18 R 9W  
BOOK PAGE 103 LINE 16

BEARDMORE-AURORA-OIL TRADING  
 #2 COLLADAY  
 SE SW SE Section 15-18S-9W  
 Rice County, Kansas

Drilled By: Beardmore Drilling Company  
 Drilling Commenced: 5-11-58  
 Drilling Completed: 5-20-58

Casing Record:

8-5/8" set at 223' with 130 sacks cement on 5-11-58. Cement circulated.

Elevation: KB 1734  
 DF 1732  
 Gr 1730

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar and Clay	30
Sand	80
Shale and Shells	200
Shale and Lime	280
Red Bed	1200
Shale and Lime	1670
Lime	1875
Shale and Lime	2695
Lime	2800
Shale and Lime	2870
Lime	3085
Lime and Shale	3170
Lime	3210
Lime and Chert	3240
Shale and Lime	3280
Rotary Total Depth	3286

TOPS


Brown Lime	2871
Lansing	2895
Sandy Conglomerate	3248 (-1513)
Simpson Shale	3265 (-1530)
Simpson Sand	3271 (-1536)
Arbuckle	3280 (-1545)

- CORE #1 3252-3260 Recovered 8' - green shaley sand with chert boulders. Trace of dead oil stain.
- CORE #2 3260-3264 Recovered 2' - conglomerate of chert, shale and sand.
- CORE #3 3264-3274 Recovered 10' - 3264-3265 conglomerate; 3265-3271 vari-colored shale, slightly sandy; 3271-3274 green waxy sandy shale and shaley sand, no show, sulphur odor.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Beardmore Drilling Company



By *Richard Beardmore*

Subscribed and sworn to before me this 3rd day of June, 1958.

My Commission Expires:  
 January 28, 1960

*Leonard P. Tolle*  
 Leonard P. Tolle-Notary Public