

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Bitting Building,
Wichita, Kansas.

Rice Kitchen County. Sec. 11 Twp. 18 Rge. 9 (E) (W)

WELL NO. _____

Lease Name. Hinkle Oil Company
Lease Owner. 919 Union National Bank Bldg., Wichita, Kansas.
Office Address. dry Total Depth of Well 3317 Feet
Character of Well (Oil, Gas or Dry) dry
Date, well, completed. 2-5 1941
Application for plugging and log of well filed. 2-5 1941
Application for plugging approved. 2-5 1941
Plugging Commenced. 2-5 1941
Plugging Completed. 2-6 1941
Reason for abandonment of well or producing formation. dry

NORTH

		0	

Locate well correctly on above 640 A. Plat

If a producing well is abandoned, date of last production. 1941
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Officer who supervised plugging of this well. Ruel Durkee
Producing formation. _____ Depth to top. _____ Bottom. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	113'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 113'
Bridged hole at bottom of surface pipe 113' with wood plug, and surface dirt. Cemented with 10 sacks cement. Filled hole with mud to 20 feet of floor, bridged hole and cemented with 10 sacks of cement.

FEB 18 1941
STATE CORP. COMM.
WICHITA, KAN.

11 18 9W
128 16

FEB 17 1941
STATE CORP. COMM.
CONSERV. DIV.

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? yes 2-17-1941

Was exception made? _____ If so describe. _____

Correspondence regarding this well should be addressed to. Hinkle Oil Company
Address. 919 Union National Bank Bldg., Wichita, Kansas.

STATE OF Sedgwick COUNTY OF Kansas, ss. J. B. Hinkle

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

NOT NOTARIZED

(Signature) J. B. Hinkle
919 Union Natl Bk (Address) 41

SUBSCRIBED AND SWORN to before me this 14 day of February, 1941

My commission expires. Jan 17, 1942. Murvel A. [Signature]
Notary Public.

KITCHEN No. 1 ^{NW} NE NE 11-18-9 Rice County, Kansas.
 Hinkle Oil Company.
 Commenced 1-24, 1941 Completed 2-5-41

Surface hole	113	cemented 113 ft. of 10" 85 sacks cement.
shale and shells	417	
Anhydrite	438	
shale	444	
shale and shells	660	
Red Rock, shale and shells	841	
shale and shells	969	
salt	1022	
shale	1100	
broken lime	1210	
lime shells and shale	1353	
lime	1444	
shale	1474	
lime	1692	
lime and shale	1876	
broken lime	1965	
shale and lime	2161	
shale	2221	
broken lime	2256	
lime and shale	2318	
shale and shells	2392	
shale	2480	
lime	2499	Top of Topeka Lime 2498
broken lime	2570	
lime	2775	
lime and shells	2889	Top of Kansas City 2883
lime	2909	
lime soft	2921	
lime	3210	
Marmaton lime	3252	
Conglomerate	3269	
conglomerate sand	3271	
conglomerate shale		
slightly green	3292	
conglomerate shale	3303	Top of Silicious Lime 3303
Silicious Lime	3317	
Cored from 3317 to 3325		

