


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Rice County, Sec. 3 Twp. 18<sup>2</sup> Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE SW  
Lease Owner A. A. OGDEN & NATIONAL MARKETING COMPANY  
Lease Name REMMERT Well No. 1  
Office Address 1726 North Topeka, Topeka, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed November 17, 1959 19  
Application for plugging filed November 17, 1959 19  
Application for plugging approved November 17, 1959 19  
Plugging commenced November 17, 1959 19  
Plugging completed November 17, 1959 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert P. Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3280 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	227'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from total depth to surface - plug at 210 feet with 20 sacks cement - mud to 40 feet another plug and 10 sacks cement to base of cellar cut off surface in bottom of cellar - filled rat hole and plug with 2 sacks cement - 3 feet down

RECEIVED  
NOV 20 1959 11-20-1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.  
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1959

Jugenia Mundell  
Notary Public.

My commission expires August 10, 1961



WELL LOG

NATIONAL MARKETING COMPANY &  
A. A. OGDEN

Commenced: November 9, 1959

Contractor: Quaker Drilling Co., Inc.

Completed: November 17, 1959

Remert No. 1  
SW NE SW Section 3-18S-9W  
Rice County, Kansas

Elevation: 1736 K. B.

Production: D. & A.

Casing Record

Set 8 5/8 inch casing at 227 feet with 150 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Clay	80	Heebner	2737 -1001
Sand	110	Toronto	2756 -1020
Grey Shale and Shells	160	Douglas	2769 -1033
Blue Shale	227	Brown Line	2858 -1122
Sand, Grey Shale & Red Bed	407	Lansing-Kansas City	2880 -1144
Anhydrite	426	Base of Kansas City	3179 -1443
Shale and Shells	1180	Conglomerate	3196 -1460
Lime and Shale	1325	Simpson Shale	3246 -1510
Sandy Lime and Shale	1540	Simpson Sand	3254 -1518
Lime and Shale	1690	Arbuckle	3264 -1528
Shale and Shells	2095	Rotary Total Depth	3280 -1544
Lime and Shale	2285		
Shale and Shells	2442		
Lime and Shale	2655		
Lime	2720		
Lime and Shale	2785		
Shale and Lime	2915		
Lime	3015		
Lime and Shale	3015		
Lime	3190		
Conglomerate	3220		
Sandy Shale	3245		
Green Shale	3250		
Sand	3262		
Shale and Sand	3264		
Dolomite	3280		

RECEIVED  
STATE CORPORATION COMMISSION

NOV 20 1959

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the driller's log of the well drilled in the SW NE SW of Section 3, Township 18 South, Range 9 West, Rice County, Kansas.

QUAKER DRILLING CO., INC.

By:

  
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 19th day of November, 1959.

  
Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:  
August 10, 1961