

Give All Information Completely

Make Required Affidavit

Mail or Deliver Report to:

Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 29 Twp. 18S Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW SW

Lease Owner ALPINE OIL & ROYALTY CO., INC.

Lease Name HAXTON Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed November 27, 1960 19

Application for plugging filed January 28, 1961 19

Application for plugging approved 1-28-61 19

Plugging commenced 1-28-61 19


Plugging completed 2-1-61 19

Reason for abandonment of well or producing formation

non-productive in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3293 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205	Cemented
				5 1/2"	3258	2720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand back from 3293 feet to 3250 feet. Dump 5 sacks cement, heavy mud, cement and rock to 200 feet 10' rock bridge and 5 sacks cement; 17 sacks cement, mud to 35 feet, dumped 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1963  
7-11-1963

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Wilson, Inc. (If additional description is necessary, use BACK of this sheet)

Address 317 N. Buffalo, Stafford, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Thomas M. McCaul

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Building, Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 63

My commission expires August 10, 1965

Notary Public



WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 11-20-60

Contractor: Quaker Drilling Co., Inc.

Completed: 11-27-60

Haxton No. 1  
SW NW SW Sec. 29-18S-9W  
Rice County, Kansas

Elevation: 1729 KB

Production: D & A

Surface Ca

Set 8 5/8" casing at 205 feet with 150 sacks cement  
Set 5 1/2" casing at 3258 feet with 100 sacks cement

(The Figures Indicate the Bottom of the Formation)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil	35	Heebner	2761 -1032
Shale	85	Brown Lime	2889 -1160
Sand	133	Lansing	2912 -1183
Clay	155	Conglomerate	3230 -1501
Shale	205	Arbuckle	3256 -1527
Shale & Red Bed	402	Rotary Total	
Anhydrite	430	Depth	3260 -1531
Red Bed and Shale	785	Cable Tool	
Shale and Shells	1385	Depth	3293 -1564
Lime and Shale	1565		
Lime and Sandy Shale	1680		
Shale and Lime	1835		
Shale	2075		
Shale and Shells	2295		
Lime and Shale	2685		
Lime	2742		
Lime and Shale	2960		
Lime	2985		
Lime and Shale	3175		
Lime	3260		

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 11 1963

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW NW SW of Section 29, Township 18 South, Range 9 West, Rice County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul  
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO BEFORE ME A Notary Public this 25th day of January, 1961.

Virginia Mundell  
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:  
August 10, 1961