

40  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 8 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Bovaird Supply

Complete Address: Box 987, Great Bend, Kansas

Lease Name W. M. Hill Well No. 1

Location NW SE Sec. 36 Twp. 19 Rge. 6 (E) (W) X

County Rice Total Depth 3354'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Apex Casing Pulling Co.

Address: 739 E. Second, Hoisington, Kansas License No. 554

Operation Completed: Hour 5 PM Day 6 Month March Year 1965

The Above well, was plugged as follows:

5 1/2" plug pushed to 3200'. Hole filled with sand to 3190' and cemented  
with 5 sacks. Hole filled with mud to 160'. Rock bridge set from 160'  
to 150' and hole cemented with 25 sacks. Hole filled with mud to 40'.  
Rock bridge set from 40' to 30' and hole cemented to base of cellar with  
10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3/8/65  
INV. NO. 749-u