

KANSAS

Form CP-3  
Rev. 6-4-68

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 7 1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

Operator's Full Name Imperial Oil Co.  
Complete Address Box 784 - City, Bend, La. - 67230  
Lease Name Huck Well No. 1-16  
Location 100's - 0 - SW - SW - Sec. 16 Twp. 30<sup>S</sup> Rge. 20 (E) (W) X  
County Flora Total Depth 5235  
Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A         
Other well as hereafter indicated       

Plugging Contractor Felso Casing Pulling  
Address Box 176 - Chase, Kans. 67524 License No. 683  
Operation Completed: Hour 2:30 pm Day 5 Month 12 Year 1978

The above well was plugged as follows:

559' - 8 5/8" casing w/ 350 sp cement - 4 1/2" casing set @ 5228'  
w/ 200 sp cement. Plug back to 5218' - Top prep @ 5105'  
Squeeze bottom w/ 35 sp cement back to 4800'  
pull 4105' of 4 1/2" casing - mix & pump 5 sac Bullu-20  
sac Gel - release plug - mix & pump 150 sp. 60/40 permit  
cement w/ 29 Gel - 39 cc to top of casing - shut in w/ 0 press.  
Pumped by  
Lewis

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 12-11-78  
INV. NO. 8707.w

Signed: Lewis Brock  
Well Plugging Supervisor