

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

November 21, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 23 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Flake of Woodman & Iannitti Drlg. Co. has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman & Iannitti

Complete Address: 706 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name: Stockham Well No. 2

Location: NE NW NE Sec. 34 Twp. 19 Rge. 8 (X) (W) (X)

County: Rice Total Depth 3466' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

Fill hole with mud. Push plug to 1100' and pump 25 sacks cement through  
drill pipe at 1100' (requested by Carey Salt Co.). Pump 25 sacks cement  
through drill pipe at 680' (requested by Carey Salt Co.). Pump 25 sacks  
cement through drill pipe at 180'. Push plug and 1/2 sack hulls to 40'  
and cap hole with 10 sacks cement. Bridge rathole and cement with 2  
sacks cement.

Very truly yours,

  
Conservation Division Agent