



15.159.04156.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 1, 1965

RECEIVED
STATE CORPORATION COMMISSION
3-8-65
MAR 8 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ben Thompson of Apex Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply

Complete Address: Box 297, Great Bend, Kansas

Lease Name: W. M. Hill Well No. 1

Location: NW SE Sec. 36 Twp. 19 Rgs. 6 (E) (W) X


County Rice Total Depth 3354' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Thompson was instructed to plug the well as follows:

Push 5 1/2" plug to 3200'. Fill hole with sand to 3190' and
cement with 5 sacks. Fill hole with mud to 160'. Set rock
bridge from 160' to 150' and cement hole with 25 sacks.
Fill hole with mud to 40'. Set rock bridge from 40' to 30'
and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent