

8-9

6-100477

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-22197.0000

SW SW SW/4 SEC. 26-20-14W
330 feet from S section line
5050 feet from E section line

Operator license# 03911

Lease: TAYLOR "B" # 3

Operator:
RAMA Operating Company
P.O. Box 159
107 West Broadway
Stafford, KS
67578

County: BARTON

Well total depth: 3535 feet 114.88
Conductor pipe: inch _____ @ _____ feet
Surface pipe: 8 5/8 inch @ 902 feet

Well type: OIL

Plugging contractor: KELSO CASING PULLING, INC. License: 06050

Address: P.O. BOX 347, CHASE, KANSAS 67524

Company to plug at: Time: 10:45 AM Date: 9 August 93

Plugging proposal received from: VERNON DUNTZ

Company: KELSO CASING

Phone: _____

Were:

Sand back to 3480 feet and 5 sacks of cmt. Shoot casing, pull to 1500 feet and spot 35 sacks cmt. Pull casing to 870 feet, spot 50 sacks cmt. Pull casing to 475 feet and circulate cmt to surface. Order 200 sacks 60/40 pozmix w/ 10% gel and 3 sx hulls.

Plugging proposal received by: DENNIS HAMEL

Plugging operations attended by agent? [YES]

Completed: hour: 2:30 PM 9 August 93

Actual plugging report:

Well plugged per recommendation. Good circulation. used 142 sacks of cement blend.

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1993

Remarks: Elevation: 1910 G Anhydrite depth: 810 feet, Annular cements plug: T
Dakota plugged: T Bottom hole plug in place (A/E/N): A
Plugged through tubing/casing: T
Arbuckle: 3532 Cemented by: ALLIED CEMENT.

I did [X] / did not [] observe the plugging.

DAVID WANN
(agent)

form CP-2/3

INVOICED
DATE 8-24-93
INV. NO. 38403