

5 020171

15.159.03287.00/00  
~~Docket 6-5960~~

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1-17-59

NWNESE, SEC. 6, T. 19 S, R. 10 (W)E

2310 feet from N (S) section line

990 feet from W (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Mooney Well # 3

Operator: Ladd Petroleum Corporation

County Rice 112.13

Name & Address Box 520

Well Total Depth 3450 feet

Great Bend, Ks. 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 1/8 feet 237'-195 SKS

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing Co, Inc. License Number \_\_\_\_\_

Address Great Bend, Kansas

Company to plug at: Hour: 1:00 PM Day: 21 Month: June Year: 1985

Plugging proposal received from Warren Irwin

(company name) Ladd Petroleum Corporation (phone) 316 792 3571

were: Pump 1 sack hulls, 75 sacks 50/50 Pozmix w/4% gel & 3% C.C., 25 Sacks Bentonite, 1 sack hulls, 5 1/2" plug, and 75 sacks 50/50 Pozmix w/4% gel & 3% C.C. into 5 1/2" casing. Pump 100 sacks 50/50 Pozmix w/4% gel & 3% C.C. into 8 1/8" - 5 1/2" annulus.

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 3:00 P Day: 21 Month: June Year: 1985

ACTUAL PLUGGING REPORT Pumped 1 sack hulls, 75 sacks 50/50 Pozmix w/4% gel and 3% C.C., 25 Sacks Bentonite, 1 sack hulls, 5 1/2" plug, and 75 sacks 50/50 Pozmix w/4% gel & 3% C.C. into 5 1/2" casing.

Pumped 100 sacks 50/50 Pozmix w/4% gel & 3% C.C. into 8 1/8" - 5 1/2" annulus.

Max Press 600 close in Press. 400 PSI. (5 1/2") Max Press 400 PSI - Close in 300 PSI. (8 1/8")

Remarks: No Casing recovered Allied # 974

(If additional description is necessary, use BACK of this form)

INVOICED (did not) observe this plugging.

DATE 7-10-85

INV. NO. 8820

Signed [Signature] CONSERVATION DIVISION Kansas (TECHNICIAN)

JUL 01 1985