

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21297-00-00
Spot: NWSESE Sec/Twnshp/Rge: 16-31S-32W
990 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: DAVIS C Well Number: 2
County: SEWARD Total Vertical Depth: 5900 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ STE
HOUSTON, TX 77227

Conductor Pipe: Size feet: \$191.75
Surface Casing: Size 8.625 feet: 1729 WITH 645 SX CMT
Production: Size 5.5 feet: 5898 WITH 1248 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/11/2001 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 3003 HULLS & 25 SX CMT FOR BOTTOM PLUG. PUMP MUD SPACER TO 1750'. PUMP 25 SX CMT. PUMP MUD SPACER. PUMP CMT FROM 600-0'.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/11/2001 12:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5490'. PERFS AT 4798-4832'. CIBP @ 5490'. 1ST PLUG PUMP 300# HULLS & 25 SX CMT FOR BOTTOM PLUG. PUMP 70 BBL MUD SPACER TO 1750'. 2ND PLUG PUMP 45 SX CMT IN SIDE 5 1/2". PUMP 18 BBL MUD SPACER TO 600'. 3RD PLUG FILL 5 1/2" TO SURFACE WITH 80 SX CMT. HOOK ONTO BACKSIDE AND PUMP 10 SX CMT. PRESSURE TO 500# AND SHUT IN. CASING PRESSURED TO 500# AND SHUT IN.

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Jim Holland PIRTP
(TECHNICIAN)

RECEIVED

DEC 31 2001

KCC WICHITA

INVOICED

DEC 26 2001

DATE

01-02-02

INV. NO.

2002061119

Form 21