

To: 1 100076  
STATE CORPORATION COMMISSION 11-8  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-175-21,487-0000  
C NW, SEC. 22, T 31 S, R 32 W/E  
3960 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4742  
Operator: Texaco E & P Inc.  
Name:  
Address P.O. Box 2700  
Pampa, TX 79066-2700

Lease Name Estelle Smith Well # 22-2  
County Seward 94.25  
Well Total Depth 2900 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 567

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X- Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H & K Plugging & Slavage License Number 31705  
Address P.O. Box 2742, Pampa, TX 79066

Company to plug at: Hour: 10 a.m. Day: 8 Month: 11 Year: 19 96

Plugging proposal received from Jimmy Connor  
(company name) Texaco E & P (phone) 806-669-8460

were: 4 1/2" at 2899' w/600 sx cement, PBDT 2852', Perfs at 2622-32, 2649-69, 2688-2710, 2726-52'  
1st plug set CIBP at 2572' with 2 sx cement on top,  
2nd plug run tubing to 617', circulate cement to surface.

11-13-96

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 8 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2572' with 2 sx cement on top,  
Loaded hole with 9.0 gel and ran tubing to 617',  
2nd plug spotted cement at 617' and circulated to surface, pulled tubing,  
3rd plug topped off with cement. Hooked onto backside and pressured to 200 psi, held 1/2 sx cement. Total cement used was 60 1/2 sx.

Remarks: Used common cement by H & K. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE NOV 14 1996

Signed Gary Winters  
(TECHNICIAN)

INV. NO. 46971 11-8 JAN 06 1997