

1091014

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-20,429-0000
C SW SW SEC. 17, T 30 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HUCK WELL # 1-17

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA

OPERATOR LICENSE # 31938

WELL TOTAL DEPTH 5243 170.40 FEET

OPERATOR: INDIAN OIL CO., INC PRODUCTION CSG: SIZE 4 1/2" @ 5240' WITH 225 SX

NAME AND PO BOX 209 SURFACE CASING: SIZE 8 5/8" @ 482' WITH 375 SX

ADDRESS MEDICINE LODGE, KS 67104

ABANDONED OIL WELL X GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:20 AM DAY: 05 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JIM SMITH

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 5171-73

SAND TO 5100' WITH 4 SX CEMENT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CEMENT -

10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CEMENT DOWN 8 5/8" CASING. MAXIMUM

PRESSURE 450#. SHUT IN WITH 350#.

INVOICED

DATE 10-26-99

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 05 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT

SAND TO 5100' WITH 4 SX CEMENT ON TOP. ALLIED PUMPED 300# HULLS - 10 SX GEL - 50 SX

CEMENT 105 gcl 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CEMENT DOWN 8 5/8" CASING. MAXIMUM PRESSURE

AT 450#. SHUT IN WITH 350#.

STATE CORPORATION COMMISSION

10-12-99 OCT 12 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3200' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3