

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20531-00-00  
Spot: CNENE Sec/Twnshp/Rge: 19-30S-20W  
660 feet from N Section Line, 660 feet from E Section Line  
Lease/Unit Name: WOOLERY Well Number: 1-19  
County: KIOWA Total Vertical Depth: 5181 feet

Operator License No.: 31938  
Op Name: INDIAN OIL CO., INC.  
Address: PO BOX 209 2507 SE US 160 HIGHWAY  
MEDICINE LODGE, KS 67104

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 606 WITH 450 SX CMT  
Production: Size 4.5 feet: 5179 WITH 200 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_ 9168.38

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/12/2001 11:25 AM  
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC  
Proposal Rcvd. from: JIM SMITH Company: INDIAN OIL Phone: (316) 886-3763

Proposed Plugging Method: PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/12/2001 12:45 PM KCC Agent: STEVE MIDDLETON


Actual Plugging Report:

PERFS AT 5108-5112'. SAND TO 5050' WITH 4 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 650#. SHUT IN PRESSURE 450#.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3810' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed 

SEP 13 2001

RECEIVED

INVOICED

SEP 14 2001

DATE 9-14-01

KCC WICHITA

INV. NO. 2002060465



Form 