

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20599-00-00
Spot: CS2NE Sec/Twnshp/Rge: 19-30S-20W
1980 feet from N Section Line, 1320 feet from E Section Line
Lease/Unit Name: WOOLERY Well Number: 3-19
County: KIOWA Total Vertical Depth: 5220 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HIGHWAY
MEDICINE LODGE, KS 67104

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 612 WITH 425 SX CMT
Production: Size 4.5 feet: 5219 WITH 200 SX CMT
Liner: Size _____ feet: _____

8169.65

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2001 9:30 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: JIM SMITH Company: INDIAN OIL Phone: (316) 886-3763

Proposed Plugging Method: PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/12/2001 10:15 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 5088-5092'. SAND TO 5050' WITH 4 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 650#. SHUT IN PRESSURE 250#.

Remarks: USED 60/40 POZMIX 6% GEL BU ACID SERVICE. RECOVERED 3820' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
SEP 19 2001
KCC WICHITA

9-19-01

Signed _____

INVOICED

(TECHNICIAN)

DATE 9-19-01 SEP 17 2001

INV. NO. 2002060503

Form CP-2/3

MP