

1 060598

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,515-^R0000

C NW NW , SEC. 20 , T 30 S, R 20 W/EX

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476

Lease Name Huck "A" Well # 1

Operator: DNB Drilling, Inc.

County Kiowa 170.30

Name & Address 535 North Oliver.

Well Total Depth 5240 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 599

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:00 am Day: 25 Month: June Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5239' PBT 5185' Perfs at 5166-70'

1st plug sand back to 5110' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 am Day: 25 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 5110' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150

RECEIVED STATE CORPORATION COMMISSION

JUL 01 1985 7-1-85

CONSERVATION DIVISION Wichita, Kansas

Maximum pressure 400 psi and shut in 100 psi

Remarks: Recovered 4464' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

(did not observe this plugging.)

INVOICED

DATE 7-10-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 8797