

1 060597

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150'W C SW NW, SEC. 20, T 30 S, R 20 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,699-0000

3300 feet from S section line

4770 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476

Lease Name Huck "A" Well # 4

Operator: DNB Drilling, Inc.

County Kiowa 168.09

Name & Address 535 North Oliver

Well Total Depth 5172 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 624

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:30 am Day: 25 Month: June Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5166'; Perfs NA

1st plug sand back to 5110 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15 pm Day: 25 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 5110' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

7-1-85

JUL 01 1985

Maximum pressure 400 psi and shut in 200 psi

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 4150' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-10-85

INV. NO. 8796

Signed Paul A. Luthi (TECHNICIAN)