

1120016

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - 097-21,145-0000

C NW NW , SEC. 23 , T 30S, R20 WÆX

4620 FEET FROM N/S SECTION LINE

4620 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 4243

LEASE NAME Brensing #1 WELL # 1A

OPERATOR: Cross Bar Petroleum, Inc.
NAME & ADDRESS: P. O. Box 20080
Wichita, KS 67208

COUNTY Kiowa 169.39

WELL TOTAL DEPTH 5212 FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 5/8 FEET 600

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Red Tiger Drilling Co. LICENSE NUMBER 5302

ADDRESS 1720 Kansas State Bank Building, Wichita, KS 67202

COMPANY TO PLUG AT: HOUR: 5:00 pm DAY: 6 MONTH: June YEAR: 19 85

PLUGGING PROPOSAL RECIEVED FROM Mike Rempe

(COMPANY NAME) Red Tiger (PHONE) 316-263-2371

Elevation 2241'

WERE: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1636'

1st plug at 1640' with 50 sx cement

2nd plug at 650' with 50 sx cement

3rd plug at 300' with 25 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

PLUGGING PROPOSAL RECEIVED BY Don Ubel

(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 6:30 pm DAY: 6 MONTH: June YEAR: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1640' with 50 sx cement, 2nd plug at 650' with 50

sx cement, 3rd plug at 300' with 25 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

6-17-85

JUN 17 1985

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: Used 60/40 Pozmix 4% gel 3% cc by Allied.

I (~~DOX~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Don C. Ubel
(TECHNICIAN)

INVOICED

FORM CP-2/3
REV. 6-83

DATE 6-20-85

INV. NO. 8628

6-6