

73R

To: 1 030715

API NUMBER 15-097, 20, 560-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C NE NW, SEC. 33, T 30 S, R 19 W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

4620 feet from S section line  
3300 feet from E section line

Operator: J. Mark Richardson  
Name & Address: 640 Century Plaza Bldg.  
Wichita Ks. 67202

Lease Name: Wheeler C Well # 1  
County: Kiowa 165.75  
Well Total Depth: 5100 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 7/8 feet 596

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor: Great Bend Casing Packers - License Number 4635

Address: Great Bend, Mo.

Company to plug at: Hour: 10:30 Day: 10 Month: 7 Year: 19 86

Plugging proposal received from Mike Comety

(company name) Great Bend Casing Packers (phone) 316-862-5449

were: 4 1/2" Set @ 5105 w/150sx Plug back T.O @ 5095

Top Reop @ 5048-87.

1st plug - Pump 2sx hulls + 50sx cement to bottom perfor.

Stop plug @ 4900' - Pull casing and squeeze well with

3sx hulls - 15sx gel -> 75sx cement -> 10sx gel -> 1sx hulls -

8 7/8 plug -> 150sx cement Plugging Proposal Received by Paul Tuhel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 AM Day: 10 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT

1st plug: pump 2sx hulls + 50sx cement + stop plug @ 4900'

2nd Pump 3sx hulls -> 15sx gel -> 75sx cement ->

10sx gel -> 1sx hull -> 150sx cement + shut in.

max pressure 400 # Shut in # @ 250

Remarks: Rec' 4015' casing Halliburton 4 1/2 Pozzini 6% gel.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-21-86

JUL 18 1986

Signed Steve Stewart (TECHNICIAN)

INV. NO. 14410

7-18-86

7-1 AUG 29 1986 SEP 29 1986