

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20, 560-0000

LEASE NAME Wheeler C

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4620 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR J. Mark Richardson

SEC. 33 TWP. 30 RGE. 19 (or (W))

ADDRESS 640 Century Plaza Bdlg., Wichita, Ks.

COUNTY Kiowa

PHONE#(316) 262-3129 OPERATORS LICENSE NO. 5414

Date Well Completed 9-02-79

Character of Well gas

Plugging Commenced 7-07-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-10-86

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 5048 Bottom 5058 T.D. 5110

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	596	0
				4 1/2	5105	4019.6

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 50 sks common & pushed plug to 4900'. 500# Pressure. Ran 3 hulls, 15 gel, 70 sks 60/40 pox mix 6% gel, 10 gel, 1 hull 8 5/8 plug & 150 sks 60/40 pox mix 6% gel, had 400# max. & 225 shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Sedgwick, ss.

J. Mark Richardson

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Mark Richardson
(Address) 640 Century Plaza, Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 86



Judy L. McMinn
Notary Public

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1986
CONSERVATION DIVISION
Wichita, Kansas

Wheeler "C" #1
C NE NW Sec 33-30S-19W
Kiowa County Kansas

Commenced: 8-22-79

Completed: 9-2-79

OPERATOR: J. Mark Richardson

Depth		Formation	Remarks
From	to		
0	285	Sand-Redbed	Ran 20 jts of 8 5/8" csg set @ 596' Cemented w/ 275 sks L.W. 3% CC 1/4# Floccel - 200 sks Common 3% CC - 2% Gel PD @ 12:30 a.m. 8-23-79
285	2320	Shale	
2320	3170	Lime-Shale	
3170	3335	Lime	
3335	4650	Lime-Shale	
4650	5100	Lime	Ran 116 jts of 10 1/2" 4 1/2" csg set @ 5105' Cemented w/ 150 sks Reg Posmix 18% Salt 3/4 of 1% CFR-2 Job Complete @ 1:00 p.m. 9-2-79
	5100 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 7th day of September, 1979.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.



RECEIVED
STATE CORPORATION COMMISSION
APR 17 1986
CONSERVATION DIVISION
Wichita, Kansas