

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

K-145-01406-0000

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas

Lease Name J. Schartz Well No. 2

Location NE NE SW Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4360

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 10A Day 3 Month 6 Year 1969

The Above well was plugged as follows:

Total Depth 4360' 8 5/8 csg set at 220' cwc 200 sk.

5 1/2 csg set at 4359' cw 125 sk cmt.

5 1/2 csg PBTD 4300' and perf. (4187-4288)

Filled 5 1/2 csg W/sd (4150-4300) Dumped 5 sk cmt W/dump bailer/ (4110-4150)

Recovered 3300' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/5/69
INV. NO. 9891-W

Signed: Geo. J. Messing
Well Plugging Supervisor