

4
KANSAS
STATE CORPORATION COMMISSION

15-415-01332-0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Equip - 7-11-69

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION-
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address 410 4th Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name J. Schartz Well No. 5

Location SW NE SW Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4317'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5:45P Day 25 Month 7 Year 1969

The above well was plugged as follows:

Total Depth 4317' 8 5/8 csg set at 210' cwc 200 sk.

5 1/2 csg set at 4315' cw 150 sk cmt.

5 1/2 csg PBD 4298' Perf. (4236-4246)

Filled 5 1/2 csg W/sd (4200-4298') Dumped 5 sk cmt with dump bailer. (4160-4200)

Cutoff and recovered 3240' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
DATE 7/28/69
INV. NO. 183-42

Signed: L. G. Munnif.
Well Plugging Supervisor