

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company., Inc. 15-145-01331-0000

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas

Lease Name J. Schartz Well No. 4

Location NW NW SW Sec. 8 Twp. 23 Rge. 17 (E) (W) XX

County Pawnee Total Depth 4324'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5:30P Day 25 Month 7 Year 1969

The Above well was plugged as follows:

Total Depth 4324' 8 5/8 csg set at 220' CWC 200 sk.

5 1/2 csg set at 4323' CW 150 sk cmt

5 1/2 csg PBTD 4308' and perf. (4234-4244)

Filled 5 1/2 csg W/sd (4200-4308) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recov. 2700' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo P. Massey  
Well Plugging Supervisor

INVOICED

DATE 7/28/69

INV. NO. 182-41