

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-145-01330-0000

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name J. Schartz Well No. 3

Location SW SW SW Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4315'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:30A Day 25 Month 7 Year 1969

The Above well was plugged as follows:

Total Depth 4315' 8 5/8 csg set at 242' cwc 200 sk

5 1/2 csg set at 4314' cw 150 sk cmt.

5 1/2 csg PBTD 4302' with top perf. (4239)

Filled 5 1/2 csg W/sd (4220-4302) Dumped 5 sk cmt W/dump bailer. (4180-4220)

Cutoff and recovered 3298' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mueser
Well Plugging Supervisor

DATE 7/28/69

INV. NO. 181-W