

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-145-01119-0000

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bk. Bldg; Wichita, Kansas 67202

Lease Name L. J. Schartz Well No. 6

Location NE SW NE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4313

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:45A Day 3 Month 6 Year 1969

The Above well was plugged as follows:

Total Depth 4313' 8 5/8 csg set at 210' cwc 200 sk.

5 1/2 csg set at 4312' cw 200 sk.

5 1/2 csg PBTD 4250' with top perf. at 4216'

Filled 5 1/2 csg W/sd (4190-4250) Dumped 5 sk cmt W/dump bailer. (4150-4190)

Shutoff and recovered 3265' of 5 1/2 csg.

Pumped thru 8 5/8 plug wontainer with 20 sk gel W/5 sk hulls, plug and 100 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6/5/69

INV. NO. 9894-u