

*AL*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-145-0118-0000

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas 67202

Lease Name L. J. Schartz Well No. 16

Location NE SW SE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4350'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5P Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4350' 8 5/8 csg set at 266' cwc 175 sk cmt.

5 1/2 csg set at 4349' cw 150 sk cmt.

5 1/2 csg perf. (4232-44)

Filled 5 1/2 csg W/sd (4220-4349) Dumped 5 sk cmt. W/dump bailer (4180-4220)

Shutoff and recovered 3267' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 500 lbs. SI pres. 350 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey  
Well Plugging Supervisor

DATE 4/21/69

INV. NO. 9635-W