

15-145-01117-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name L. J. Schartz Well No. 15

Location G W/2 W/2 NE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4300

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 1P Day 3 Month 6 Year 1969

The Above well was plugged as follows:

Total Depth 4300' 8 5/8 csg set at 208' cwc 200 sk.

5 1/2 csg set at 4298' cw 150 sk cmt.

5 1/2 csg PBD 4265 With top perf. (4199)

Filled 5 1/2 csg W/sd (4175-4265) Dumped 5 sk cmt W/dump bailer. (4135-4175)

Shutoff and recovered 3200' of 5 1/2 csg.

Pumped thru 8 5/8 plg. container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red F. Massey
Well Plugging Supervisor

DATE 6/5/69
INV. NO. 9898-W