

4

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1969  
CONSERVATION DIVISION  
Wichita, Kansas

15-145-61114-0000

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas 67202

Lease Name L. J. Scharzt Well No. 12

Location C EL SE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4325

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2:30P Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4325' 8 5/8 csg set at 215' cwc 200 sk.

5 1/2 csg set at 4323' cw 175 sk cmt.

5 1/2 csg PBTD 4295 with top perf. (4208)

Filled 5 1/2 csg W/d (4190-4295) Dumped 5 sk cmt W/dump bailer. (4150-4190)

Cutoff and recov. 3330' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 400 lbs. SI pres. 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE 4/21/69

INV. NO. 9633-W