

15-145-01113-0000

Form CP-3
Rev. 6-26-62



KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas 67202

Lease Name L. J. Schartz Well No. 11

Location NW SE SE Sec. 8 Twp. 23 Rge. (E) (W)17

County Pawnee Total Depth 4344

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4:15P Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4344' 8 5/8 csg set at 221' cwc

5 1/2 csg set at 4342' cw 150 sk cmt.

5 1/2 csg PBD 4330' and perf. (4245-53)

Filled 5 1/2 csg W/sd (4225-4330) Dumped 5 sk cmt W/dump bailer. (4185-4225)

Cutoff and recovered 3270' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 800 lbs. SI pres. 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 4/21/69

INV. NO. 9632-4