

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company, Inc. 15-145-01112-0000

Complete Address: 410 4th National Bank Bldg, Wichita, Kansas

Lease Name L. J. Schartz Well No. 10

Location SE NW SE Sec. 8 Twp. 23 Rge. 17 (E) (W)XX

County Pawnee Total Depth 4288'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:15A Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4288' 8 5/8 csg set at 2161' cwg 200 sk cmt.

5 1/2 csg set at 4286' cw 150 sk cmt.

5 1/2 csg PBD 4258 1/2 and perf (4224-4234)

Filled 5 1/2 csg W/sd (4200-4258 1/2) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3290' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 400 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 4/21/69

INV. NO. 9631-11