

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1969

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-145-01111-0000

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name L. J. Schartz Well No. 9

Location S1/4 NE 1/4 NE 17 E Sec. 8 Twp. 23 Rge. 17 (E) (W) XX

County Pawnee Total Depth 4283

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 9:30A Day 28 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 4283' 8 5/8 csg set at 214' cwc 200 sk.

5 1/2 csg set at 4281' cw 150 sk cmt.

5 1/2 csg FBTD 4263 with perf (4200-4208)

Filled 5 1/2 csg W/sd (4175-4263) Dumped 5 sk cmt W/dump bailer (4135-4175)

Cutoff and recovered 3400' of 5 1/2 csg.

Pumped thru 8 5/8 plug container With 20 sk gel W/5 sk hulls, Plug and 100 sk comm

cement. Max. pres. 500 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo P. Massey
Well Plugging Supervisor

DATE 3/4/69

INV. NO. 9409-W