

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
Rev. 6-26-62

15-145-61109-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company
Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas 67202
Lease Name J. Schartz Well No. 7
Location C NL SW Sec. 8 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4310
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling Co.
Address: Box 405 Chase, Kansas License No. 436
Operation Completed: Hour 4:30P Day 25 Month 7 Year 1969

The Above well was plugged as follows:

Total Depth 4310' 8 5/8 csg set at 218' cwc 200 sk.
5 1/2 csg set at 4308' cw 150 sk cmt.
5 1/2 csg PBTD 4296' and perf. (4221-4229)
Filled 5 1/2 csg W/sd. (4200-4296) Dumped 5 sk cmt W/dump bailer. (4160-4200)
Shutoff and recovered 3500' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ray F. Massey
Well Plugging Supervisor

DATE 7/28/69
INV. NO. 185-4