

KANSAS

Form CP-3  
Rev. 6-26-62



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-145-01107-0000

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name L. J. Schartz Well No. 5

Location NW NW NE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4282

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor:        Knight Casing Pulling

Address:        Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3P Day 3 Month 6 Year 1969

The Above well was plugged as follows:

Total Depth 4282' 8 5/8 csg set at 204' cwc 175 sk.

5 1/2 csg set at 4281' cw 150 sk cmt.

5 1/2 csg perf. (4259)

Filled 5 1/2 csg W/sd (4225-4281) Dumped 5 sk cmt W/dump Bailer. (4185-4225)

Shutoff and recovered 3320' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 6/5/69  
INV. NO. 9893-W