

KANSAS

Form CP-3
Rev. 6-26-62

15-145-01106-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company Inc.

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name L.J.Shartz Well No. 4

Location NE NE SE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4354

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3:30P Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4354' 8 5/8 csg set at 222' cwc 175 sk

5 1/2 csg set at 4351' cw 175 sk cmt.

5 1/2 csg perf. 4239 Filled 5 1/2 csg W/sd (4200-4354) dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recov. 3311' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 500 lbs. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ray F. [Signature]
Well Plugging Supervisor

DATE 4/21/69
INV. NO. 96.30-11