

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co., Inc. 15-145-01105-0000

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name L. J. Schartz Well No. 3

Location SW SW SE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4347

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling, Co.

Address: Box 405 Ghase, Kansas License No. 436

Operation Completed: Hour 10:30A Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4347' 8 5/8 csg set at 240' cwc 175 sk.

5 1/2 csg set at 4346' cw 125 sk cmt.

5 1/2 csg PBTD 4330' and perf 4285'

Filled 5 1/2 csg W/sd (4270-4330) Dumped 5 sk cmt W/dump bailer. (4230-4270)

Cutoff and recov. 3390' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 500 lbs. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Ken F. Massey
Well Plugging Supervisor

INVOICED

DATE 4/21/69
INV. NO. 9629-4