

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-145-01104-0000

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name L. J. Schartz Well No. 2

Location NW NW SE Sec. 8 Twp. 23 Rge. 17 (E) (W) XX

County Pawnee Total Depth 4350'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12N Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4350' 8 5/8 csg set at 216' CWC 200 sk.

5 1/2 csg set at 4349' cw 150 sk cmt.

5 1/2 csg perf. 4207--

Filled 5 1/2 csg W/sd (4200-4350) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3360' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 500 lbs. SI pres. 350 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/21/69
INV. NO. 9628-u

Signed: [Signature]
Well Plugging Supervisor